

RESOLUTION NO. 08-09


Commissioner Lawson introduced the following Resolution and moved its adoption:

RESOLUTION ORDERING ADVERTISEMENT FOR A CONSTRUCTION BID.

BE IT RESOLVED BY THE BOARD OF CITY COMMISSIONERS OF THE CITY OF WILLISTON, NORTH DAKOTA:

That the Board of City Commissioners orders the advertisement for construction bids for **WATER, SEWER, STREET & ALLEY IMPROVEMENT DISTRICT 08-2.**

The motion for the adoption of the foregoing Resolution was duly seconded by Commissioner Bogar, and upon vote being taken thereon, the following Commissioners voted AYE: Lawson, Bogar, Underhill and the following voted NAY: None Absent and not voting: Bekkedahl, Koeser. Whereupon said motion was declared duly passed and adopted this 12th day of February 2008.



Frank Underhill, Vice-President
Board of City Commission

ATTEST:


John Kautzman, City Auditor

ADVERTISEMENT FOR BIDS
FOR
WATER, SEWER, STREET & ALLEY IMPROVEMENT DISTRICT 08-2
Williston, North Dakota

Notice is hereby given that sealed bids for the completed construction of Water, Sewer, Street & Alley Improvement District 08-2 for City of Williston, North Dakota, will be received at the Office of the City Auditor, in the Williston City Hall, P.O. Box 1306, until 3:00 P.M., Central Daylight Saving Time, March 20, 2008. At that time, the bids will be opened in the City Commission Meeting Room at the Williston City Hall, 22 East Broadway, Williston, North Dakota, and read aloud.

The project consists of the following approximate principal quantities:

Section I – Alley Improvements - Block 6 Original Townsite—Remove and replace 333 square yards of 6" reinforced concrete alley.

Section II – 7th Avenue East Street Improvements—Part A Street Improvements—906 square yards of profile asphalt milling, 906 square yards of 2" H.B. asphalt fabric overlay. **Part B Concrete Repair**--48 square yards of 6" Concrete Driveway and 68 lineal feet of curb and gutter.

Section III – 19th Street West Street Improvements—Part A Street Improvements—1,194 square yards of profile asphalt milling, 1,194 square yards of 1 ½" H.B. asphalt overlay, and 400 feet of street reconstruction including 1,500 cubic yards of excavation, 2,800 square yards of geotextile fabric, 800 lineal feet of 4" underdrain, 1,175 cubic yards of 18" aggregate base, 1,634 square yards of 4" H.B. asphalt pavement, 866 lineal feet of curb & gutter, 41 square yards of 4" concrete sidewalk and 241 square yards of 6" concrete driveway. **Part B Sewer Improvements**—200 lineal feet of 6" sewer and one manhole.

Section IV – Avenue R & S Street Improvements—Part A Avenue R Street Improvements—250 cubic yards of excavation, 800 square yards of geotextile separation fabric, 250 cubic yards of 12" aggregate base, 773 lineal feet of reinforced mountable curb & gutter, and 319 square yards of 8" reinforced concrete driveway and valley gutter. **Part B Avenue S Street Improvements**—385 cubic yards of excavation, 1218 square yards of geotextile separation fabric, 385 cubic yards of 12" aggregate base, 674 lineal feet of reinforced mountable curb & gutter, 294 square yards of 8" reinforced concrete driveway and ditch cleaning.

Section V – 12th Avenue East Street Improvements—281 lineal feet of 12" PVC water main, two 6" hydrants, two 12" gate valves, 4 water main connections, 46 lineal feet of 12" PVC storm sewer, one manhole, two inlets, 1,652 square yards of profile asphalt milling, and 2" H.B. asphalt overlay. 2,155 cubic yards of excavation, 4,555 square yards of geotextile separation fabric, 1,280 lineal feet of 4" underdrain, 2,155 cubic yards of 18" aggregate base, 3,734 square yards of 4" H.B. asphalt pavement, 223 square yards of 4" H.B. asphalt pavement, 223 square yards of 6" concrete driveway, 84 square yards of 8" concrete pavement, and access trail.

Section VI – 23rd Street West Water, Sewer, and Street Improvements—377 lineal feet of 12" PVC water main, two 6" hydrants, two 12" gate valves, 307 lineal feet of 1" P.E. water service lines, nine 1" curb stops, 377 lineal feet of 12" PVC sewer main, one sewer manhole, 291 lineal feet of 6" PVC sewer service, 377 lineal feet of 24" RCP storm sewer, 38 lineal feet of 12" PVC storm sewer, one storm sewer manhole, two storm inlets, 500 cubic yards of excavation, 1,750 square yards of 6" aggregate base, 1,475 square yards of 4" H.B. asphalt pavement, 759 lineal feet of concrete curb & gutter and 37 square yards of 6" concrete alley return.

Section VII – 24th Street West Water Improvements--805 lineal feet of 8" PVC water main, 73 lineal feet of 6" PVC water main, two 8" gate valves, two 6" gate valves, two 6" hydrants, and one sewer manhole.

Section VIII – Main Street Valve Replacement—Replace four existing 6" gate valves, install one new 10" gate valve, and 225 square yards of concrete pavement repair.

Section IX – Miscellaneous Asphalt Patching—1,000 tons of miscellaneous asphalt patching and 3,000 square yards of asphalt milling.

To order specifications & plans or for further information contact the Engineering Department at 809 5th Street East, P.O. Box 2437, Williston, ND 58802-2437, or call 701-577-6368. ALL BIDDERS are required to

view the proposed project site area in order to familiarize themselves with the details of the area prior to submitting a bid.

Copies of the bid forms, drawings, specifications, and contract documents may be obtained from the Engineering Department for payment of a non-refundable \$40.00 fee.

Each bid is to be submitted on the basis of cash payment for the work and is to be enclosed in a sealed envelope addressed to the City Auditor. Each bid shall be accompanied by a Bidder's Bond in a sum equal to 5% of the full amount of the bid, executed by the BIDDER as principal and by a surety company authorized to do business in this State, conditioned that if the principal's bid be accepted and the contract be awarded to him, he within 10 days after Notice of Award, will execute and effect a contract in accordance with the terms of his bid and provide a Performance and Payment Bond in the amount of 100% of the Contract Price with a corporate surety approved by the Owner.


The Bid Bond and Contractor's License Renewal Certificate shall be submitted in a separate sealed envelope attached to the outside of the Bid Envelope. Bidders must be licensed for the highest amount of their bid.

Each Bid shall be marked on the outside of the envelope, the date of the proposal, the name of the Bidder, and acknowledgment of any Addendums that were received. The right is reserved to reject any or all bids, and to waive any informality in any bid and to hold bids for a period not to exceed 30 days from said date of opening of bids.

Dated this 12th day of February, 2008.

CITY OF WILLISTON, NORTH DAKOTA

BY:



John Kautzman, City Auditor

By Order of the Board of City Commissioners,

City of Williston, North Dakota

Publish:

Herald--February 17 & 24, 2008.

Construction Bulletin--February 25 & March 3, 2008.